

Padma View Specialised Hospital Extension

Tender Specification & Preliminaries · দরপত্র বিবরণী

PVH-2026 · Revision C · Issued 14 September 2026

1. Preliminaries and general conditions

1.1 Working hours

Working hours on site are 08:00 to 18:00, Saturday to Thursday. **Friday is the weekly holiday** and no work is permitted on Friday or on public holidays. Noisy operations — anything above **75 dB(A) at the site boundary** — are further restricted to **09:00 to 17:00**, because the adjoining outpatient department remains in clinical use throughout the works.

1.2 Deliveries and site access

All deliveries shall be booked with the site office at least 48 hours in advance. The single site access is from Road 4, Sector 11. No deliveries are permitted between 07:30 and 09:00, when patients are arriving.

1.3 Monsoon provisions

From June to September the Contractor shall maintain adequate covering, pumping and temporary drainage for open slabs and castings. Claims for weather delay are admissible only with Bangladesh Meteorological Department records for the days claimed.

2. Information and communication

2.1 Requests for information

The Contractor shall submit Requests for Information through the project information system. The consultant team shall respond within **7 working days**. An RFI that affects the critical path shall be marked **Urgent** and answered within **3 working days**. No extension of time arises from an RFI raised later than 15 working days before the information is required.

2.2 Samples and shop drawings

Shop drawings, product data and samples shall be submitted not less than 10 working days before the material is required on site. The review period is 7 working days. A submittal returned as 'Revise and Resubmit' restarts the review period in full.

2.3 Progress reporting

The Contractor shall issue a written progress report by the third working day of each month, covering progress against the accepted programme, procurement status, open RFIs, safety statistics, and any matter likely to give rise to a claim for additional time or money.

3. Materials and workmanship

3.1 Concrete

Location	Grade	Cover	Notes
Piles and pile caps	4000 psi (C30/37)	75 mm	Sulfate-resisting cement, slump 150–180 mm
Grade beams	4000 psi (C30/37)	50 mm	—
Slabs and beams, Levels 1–5	3500 psi (C25/30)	25 mm	To BNBC 2020
Columns	4000 psi (C30/37)	40 mm	—
Blinding	1500 psi	—	75 mm minimum thickness

All concrete shall be supplied from a BSTI-accredited ready-mix plant. One set of cylinder tests shall be taken per 50 cubic metres or per pour, whichever is the more frequent, with 7-day and 28-day results issued to the consultant.

3.2 Aluminium glazing

The glazing system shall be thermally broken aluminium with 6 mm + 12 mm air gap + 6 mm double glazed units, tested for air permeability. A full-size **sample panel** shall be erected on site and approved in writing by the Architect before manufacture is released. **The manufacturing lead time is 12 weeks from written approval of the sample panel.**

3.3 Operation theatres

The two modular operation theatres shall achieve **ISO 14644-1 Class 7**, with a minimum of **20 air changes per hour** and **+15 Pa positive pressure** relative to adjacent areas. HEPA filters shall be verified by an independent agency after installation and before handover.

4. Health, safety and environment

Requirement	Standard	Frequency
Site induction	Every person before first access	Once per person
Toolbox talk	Recorded, signed register	Weekly
Scaffold inspection	Competent person, written record	Every 7 days
Work at height permit	Above 3 metres	Each occasion
Accident reporting to the Employer	Within 24 hours	Each occurrence
Dust and noise monitoring	75 dB(A) at the boundary	Continuous

5. Completion and handover

5.1 Commissioning

All mechanical and electrical systems shall be commissioned to the relevant standards. Witnessed commissioning shall be completed not less than 4 weeks before the date for completion.

5.2 Handover documentation

Deliverable	Due	Format
Draft O&M manuals	8 weeks before completion	PDF, indexed
Final O&M manuals	At completion	PDF and 2 hard copies
As-built drawings	At completion	PDF and native CAD
Test and commissioning certificates	2 weeks before completion	PDF
RAJUK occupancy certificate	At completion	Original
Fire Service clearance	Before commissioning	Original
Building user training	2 weeks before completion	4 sessions

5.3 Practical completion

Practical completion shall not be certified until all commissioning is complete and the documentation above has been accepted. The date for completion is **30 June 2027**. 0.05% per day, capped at 10% of the contract sum applies thereafter.